



SCOPE OF WORK

VILLAGE OF AGENCY – RED BIRD DRIVE STREET PAVING PROJECT

1. Project Overview

The Village of Agency is soliciting bids for the improvement and paving of Red Bird Drive. The work includes all labor, materials, equipment, and supervision necessary to complete the project in accordance with applicable standards and specifications.

2. Project Location

Red Bird Drive, within the municipal limits of the Village of Agency, Missouri.

3. Extent of Work

The contractor shall provide all labor, materials, equipment, and supervision necessary to prepare existing chip seal roadways and install a **2-inch asphalt overlay**, in accordance with applicable standards such as those from the Missouri Department of Transportation.

4. Description of Work

The contractor shall perform all work necessary to complete **milling as needed with 2-inch compacted thickness of hot mix asphalt**, also including but not limited to:

- **Site Preparation:**
Clearing and grubbing as needed; removal of debris; protection of existing utilities and adjacent properties.
- **Demolition/Removal:**
Milling, removal, and proper disposal of existing pavement, base material, and unsuitable subgrade where required.
- **Subgrade Preparation:**
Grading, shaping, and compaction of subgrade to meet specified elevations and compaction requirements.
- **Base Installation:**
Placement and compaction of aggregate base material to specified thickness and density.
- **Pavement Installation:**
Placement of asphalt pavement (or other specified surface), including binder and surface courses, in accordance with Missouri Department of Transportation (MoDOT) standards.
- **Edge Work and Shoulders:**
Construction and grading of shoulders, tie-ins to existing roads, driveways, and adjoining surfaces.
- **Traffic Control:**
Provision and maintenance of traffic control devices, signage, and safety measures throughout the duration of the project in compliance with MUTCD standards.
- **Restoration:**
Final grading, seeding, and restoration of disturbed areas, including right-of-way and adjacent properties.

- **Cleanup:**
Removal of all construction debris, equipment, and excess materials; final site cleanup upon project completion.

5. Materials and Standards

All materials and workmanship shall conform to current MoDOT specifications, and any additional requirements set forth by the Village of Agency.

6. Contractor Responsibilities

- Obtain all necessary permits and approvals.
- Coordinate with utility companies as needed.
- Maintain a safe work environment in compliance with OSHA standards.
- Protect existing infrastructure and repair any damage caused by construction activities.
- Proof of insurance and any required bonding must be provided.

7. Additional Provisions

The Village reserves the right to modify the scope as necessary and to reject any work not meeting specifications.

8. Completion

The Village would like this completed by September 30, 2026.

END OF SCOPE OF WORK

Sealed bids must be submitted to the Village Clerk no later than **5:00pm** on **April 27, 2026**. Bids will be opened and read on April 27, 2026, at 6:00pm.

Contact Kerri Krumme at 816-261-3066 or email villageclerk@yahoo.com